



## CASE STUDY //

### Salford Gateway

This project was recently handed over in August 2016, the 16 Month contract proving to be our largest mechanical install to date. The project consisted of a large roof top plant area where by MWA installed large heavy gauge welded pipework up to 12" in diameter, full installation of the heating system, chilled water / cooling system, domestic water services, boosted cold water services, rain water harvesting and above ground drainage. The installation included industry leading controls and design to make this landmark installation our best yet.